



GOVERNMENT OF WEST BENGAL
OFFICE OF THE DISTRICT MAGISTRATE &
DISTRICT PROGRAMME COORDINATOR
PURBA MEDINIPUR : : TAMLUK
(MGNREGS CELL)

PH: 03228 263990/263017(FAX). Toll Free Help Line No. – 1800-3453202
E-mail: nrega_tamluk@rediffmail.com/mgnrega.tamluk@gmail.com

Memo No.: 606/ENGG/MGNREGS/ XXXXII-

Dated. 23/10/17

NOTICE INVITING TENDER

N.I.T. No.- 03 of MGNREGS/Purba Medinipur of 2017-18

Open Tender of rates are hereby invited by the District Nodal Officer, MGNREGS, Tamluk, Purba Medinipur from all the **enlisted bonafide** suppliers / contractors for the following works with **50%** payment / credential certificate of similar nature of work in last three years.

The Tender will be opened in presence of the Tenderer or their authorized representative.

Sl. No.	Name of work	Tender amount	Earnest Money	Cost of Tender Paper	Time of Completion
1.	CONSTRUCTION OF HOSPITAL SIDE INTERLOCKING PAVER BLOCK PAVEMENT FROM HSPITAL MORE PWD ROAD SIDE TO INFRONT OF RAKHAL MEMORIAL STADIUM ROAD UNDER PURBA MEDINIPUR.	Rs. 498474.00	Rs.10000.00	Rs.500.00	15(fifteen days)

Tender should be placed in sealed cover super scribed with the name of the work. The Tenderer will place their Tender to the undersigned.

Tender document shall consist of (a) Notice inviting Tender (b) Schedule of works.

Tender paper will be available from the office of the undersigned on before **30.10.2017 up to 5.00pm.** (Except holidays). No tender paper will however be issued on the date fixed for opening the tender. Tenderer(s) will have to produce **attested copies valid income tax (SARAL), sales tax, professional tax, vat clearance certificate & credential certificate etc.**

1. Last date of Application**30.10.2017 up to 2.00pm.**
2. Date of issue of tender paper**30.10.2017 up to 5.00pm.**
3. Date of receiving of tender paper..... **31.10.2017 up to 3.00 pm.**
4. Date of opening of tender paper**01.11.2017 at 5.00 pm.**

INSTRUCTION FOR THE BIDDERS:

1. The Tenderer shall quote his rate on the basis of percentage less / at per / above to the schedule rate / item wise rate.
2. The rate offered shall be considered as inclusive of all taxes and charges as per Government rules and plants and machineries payable to the Central Govt. or State Govt. or any local body having jurisdiction. The rate should be given both in figure and words. Any correction / cancelled on of any entry on the Tender paper without the attestation by the concern Tender will liable to be rejected.
3. Defective Tender or ambiguous Tender and Tender not submitted within the stipulated date & time, will be summarily rejected as or without comparing other rates. Besides the District Nodal

Officer, MGNREGS, Tamluk, Purba Medinipur reserves the right of rejecting any tender or all the Tenders as whole or partially without assigning any reason thereof.

4. The intending Tender shall have to deposit earnest money along with the Tender Paper 2.0% of estimated amount and cost of Tender Paper separately in favour of the 'PURBA MEDINIPUR EMPLOYMENT GUARANTEE FUND' payable at 'STATE BANK OF INDIA, TAMLUK RAILWAY STATION BRANCH, PURBA MEDINIPUR' as the case may be, by Call Deposit or Bank Draft etc. at the discretion of the prescribed authority.
5. Any Tender without these documents & earnest money deposit will liable to be rejected summarily before comparison
6. The earnest money will be returned to the unsuccessful Tender after finalization of the Tender. The cost of supplying the articles in any quantity to the site as specified by the S.A.E concerned or order by the undersigned shall be borne entirely by the manufacturer / supplier, who has been so ordered to supply. Such cost of supply should include, among other charges, the charges of transportation / carriage / loading / unloading handling, loss, damage in transport.
7. If any Tender withdraws his / her Tender before acceptance without giving any satisfactory explanation for such withdrawal, will render him / her disqualified to participate in Tender for a period of next 6 (six) months. The rate offered by the Tenderer will remain valid up to completion of work from the date of issue of the work / supply order.
8. The security deposit @ 8.0% of the bill value should be deducted from each and every bill.
9. In case, any Tenderer fails to supply / work of any article / material which is directed to so supply within the prescribed time / period as mentioned in the work / supply order the same shall be treated as cancelled and in the case, the earnest money shall be forfeited.
10. The contractor / manufacturer / supplier who has been ordered to supply article in any quantity or to complete any work shall be liable to replace the total supplied quantity or a part thereof, at the discretion of the undersigned. If after words, found to be defective, and / or other the specification and, or beyond, as mentioned in the supply order.
11. The undersigned is authorized by relevant Acts and rules to deduct Income Tax (with surcharge) and Sales Tax from the bills of the manufacturer / supplier at the prescribed rates.
12. The undersigned reserves the right to cancel this Tender process at any stage and at any time, without showing any reason there of.

**District Nodal Officer, MGNREGS
Tamluk, Purba Medinipur.**

Memo No.: ^{606/K6} ENGG/MGNREGS/ XXXXII-~~XXXX~~

Dated. 23/10/17

1. The DIO, NIC with a request to publish it at District website.
2. The APM(MIS), MGNREGS with a request to publish it at our MGNREGA website.
3. CA to District Magistrate, Purba Medinipur.
4. CA to Additional District Magistrate (Dev).
5. Office Notice Board
6. Guard File


**District Nodal Officer, MGNREGS
Tamluk, Purba Medinipur.**


**PROPOSED ESTIMATE OF CONSTRUCTION OF HOSPITAL SIDE INTERLOCKING PAVER
BLOCK PAVEMENT FROM HSPITAL MORE PWD ROAD SIDE TO INFRONT OF RAKHAL
MEMORIAL STADIUM ROAD UNDER PURBA MEDINIPUR.**

Sl. No.	Description of the Item	Calculation	Total Quantity	Unit	Rate	Amount
1	Dismantling of existing structures like culverts, bridges, retaining walls and other structures comprising of brick masonry, including disposal of unserviceable material and stacking the serviceable material with all lift and lead of 1000 m as per Technical Specifications Clause 202 for Rural Roads of MORD. (II) By Mechanical Means a) Cement Concrete	$210.0 \times 1.5 \times 0.275 = 86.625 \text{ Cum.}$	86.63	Cum.	470.00	40713.75
2	125 mm. thick brick work with 1st class bricks in cement mortar (1:4) in ground floor.	$420 \times 375 = 157.5 \text{ Sqm.}$	157.50	Sqm.	765.00	120487.50
3	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor). [Excluding cost of chipping over concrete surface] (i) With 1:6 cement mortar (c) 15 mm thick plaster	$420.0 \times 0.400 = 168 \text{ Sqm}$	168.00	Sqm.	147.00	24696.00
4	Neat cement punning about 1.5mm thick in wall, dado, window sill, floor etc.	$500.0 \times 0.55 = 275$	275.00	Sqm.	38.00	10450.00
5	Supplying and laying Polythene Sheet (150gm / sq.m.) over damp proof course or below flooring or roof terracing or in foundation or in foundation trenches.	$420.0 \times 0.5 = 210 \text{ sqm.}$	210.00	sqm.	25.00	5250.00
7	Filling in foundation or plinth by fine sand in layers not exceeding 150 mm as directed and consolidating the same by thorough saturation with water, ramming complete including the cost of supply of sand. (payment to be made on measurement of finished quantity) (B) Do - by fine sand	$420.0 \times 0.3 \times 0.1 = 12.6$	12.6	%Cum.	74726.00	9415.48
8	Cement concrete with graded jhama khoa (30 mm size) excluding shuttering In ground floor and foundation. (a) 1:3:6 proportion	$420.0 \times 0.25 \times 0.075 = 7.875 \text{ Cum.}$	7.875	No	5303.00	41761.13
9	Supplying & laying interlocking designer paver block of any shade and of approved quality as per IS: 1237-1980 laid in pattern as directed in pavement, footpath, driveway, etc including necessary underlay complete in all respect with all labour and material. [Border concrete if necessary to be paid separately]. (b) 40 mm thick block (over 150 mm medium sand bed including cost of sand but excluding cost of earthwork in excavation or dismantling of existing hard surface if necessary) (i) Grey	210.0×1.20	252	Sqm.	975.00	245700.00
Total Amount						498473.85

Say Rs. 498474.00

(Rupees Four Lakh Ninetyeight Thousand Four Hundred Seventyfour Only.)


 Signature of Authority
 District Nodal Officer, MGNREGS
 Purba Medinipur.


 Vetted By
 Assistant Engineer
 District MGNREGS Cell


 Prepared By
 Technical Assistant
 District MGNREGS Cell